



R&D on Beam Injection and Bunching Scheme in the Fermilab Booster


Chandra Bhat
Fermilab




Acknowledgements

W. Pellico, C. Drennan, K. Triplett, S. Chaurize,
K. Seiya, F. Garcia, B. Hendricks, T. Sullivan and A. Waller


"HB2016, Malmö, Sweden, 3-8 July 2016"




Fermilab, US Premier Particle Physics Laboratory




**Booster:
0.4-8 GeV
Accelerator**



Fermilab, US Premier Particle Physics Laboratory




**Booster:
0.4-8 GeV
Accelerator**



Upgrade Path for Power on Target



Parameter	PIP Completed	PIP-II
Injection Energy (KE) (GeV)	0.4	0.8
Extraction Energy KE (GeV)	8	8
Injection Intensity (p/pulse)	4.52E12	6.63E12
Extraction Intensity (p/pulse)	4.3E12	6.44E12
Bunch Removed	3	3
Efficiency (%)	95	97
Booster repetition rate	15 Hz	20 Hz
Booster Beam Power at Exit (kW)	94	184
MI batches	12 per 1.33 sec	12 per 1.2 sec
NOvA beam power	700 kW	1200 kW
Rate availability for other users (Hz)	5	8
Booster flux capability (protons/hr)	~ 2.3E17	~ 3.5E17
Laslett Tune shift at Injection	≈ -0.072	≈ -0.105
Longitudinal energy spread	< 6 MeV	< 6 MeV
Transverse emittances (p-mm-mrad)	< 14	18
Booster uptime	> 85%	> 85%




Present inj. point at L1
New inj. point at L11

Upgrade Path for Power on Target



Parameter	PIP Completed	PIP-II
Injection Energy (KE) (GeV)	0.4	0.8
Extraction Energy KE (GeV)	8	8
Injection Intensity (p/pulse)	4.52E12	6.63E12
Extraction Intensity (p/pulse)	4.3E12	6.44E12
Bunch Removed	As of June 23 with	
Efficiency (%)	95	97
Booster repetition rate	15 Hz	20 Hz
Booster Beam Power	& EIS in Operation we have reached	
MI batches	12 per 1.33 sec	12 per 1.2 sec
NOvA beam power	701 kW	1200 kW
Rate availability for other users (Hz)	5	8
Booster flux capability (protons/hr)	~ 2.3E17	~ 3.5E17
Laslett Tune shift at Injection	≈ -0.072	≈ -0.105
Longitudinal energy spread	< 6 MeV	< 6 MeV
Transverse emittances (p-mm-mrad)	< 14	18
Booster uptime	> 85%	> 85%




Present inj. point at L1
New inj. point at L11

Upgrade Path for Power on Target



Parameter	PIP Completed	PIP-II
Injection Energy (KE) (GeV)	0.4	0.8
Extraction Energy KE (GeV)	8	8
Injection Intensity (p/pulse)	4.52E12	6.63E12
Extraction Intensity (p/pulse)	4.3E12	6.44E12
Bunch Removed	As of June 23 with	
Efficiency (%)	95	97
Booster repetition rate	15 Hz	20 Hz
Booster Beam Power	701 kW & EIS in Operation we have reached	
MI batches	12 per 1.33 sec	12 per 1.2 sec
NOvA beam power	701 kW	1200 kW
Rate availability for other users (Hz)	5	6
Booster flux capability (protons/hr)	~ 2.3E17	~ 3.5E17
Laslett Tune shift at Injection	~ 0.75	~ 1.0
Longitudinal energy spread	< 6 MeV	< 6 MeV
Transverse emittances (p-mm-mrad)	< 14	18
Booster uptime	~ 55%	~ 30%



Present inj. point at L1
New inj. point at L11

The Booster will remain as the workhorse in the Fermilab Accelerator Complex at least for next two decades




Are there Innovative ways to Increase the Booster Beam Intensity beyond PIP?




Are there Innovative ways to Increase the Booster Beam Intensity beyond PIP?

- New Injection and Bunching Scheme
- Beam Simulations
- New Scheme in Operation
- Issues and Mitigation ← Also Relevant to PIP-II
- Projections
- Summary

Beam Injection in the Booster for the past 45 years




Beam Injection in the Booster for the past 45 years



Issues: A limited time for Beam Capture & Acceleration. RF manipulations are non-adiabatic \leftarrow $>100\%$ emittance dilution, $\sim 8-10\%$ beam loss and large RF power

Schematic of the Early Injection in the Booster with a pseudo front-porch



C. M. Bhat, IPAC2015

Beam Injection & Capture



- Needs a good understanding of
 - Properties of the beam from the LINAC
 - ❖ Beam Energy Spread, ΔE (full)
 - ❖ H and V Transverse Emittances
 - Acceptance at Injection
 - ❖ Momentum Acceptance in the Booster
 - ❖ Transverse Acceptance

Beam Injection & Capture





□ Needs a good understanding of





➤ **Properties of the beam from the LINAC**

- ❖ Beam Energy Spread, ΔE (full)  = 1.25 MeV
 - ❖ H and V Transverse Emittances *i.e.*, $\epsilon_l(\text{Inj}) \approx 0.033$ eVs/Bunch
- HB2016 MOPL020

➤ **Acceptance at Injection**

- ❖ Momentum Acceptance in the Booster  5.4 MeV (± 0.4 MeV)
- ❖ Transverse Acceptance  H: 50 π -mm-mr
V: 30 π -mm-mr


ESME Simulations of EIS



ESME Simulations of EIS




ΔE - Δt Phase space (7.3E12p/Booster Batch)



ESME Simulations of EIS



Line-Charge Dist.



-2

0

2

Azimuthal Angle(deg)



- We revisited many LLRF parameters
 - Curves: Radial-position feedback, Voltage and RF frequency etc.
 - Turn-on time for many parameters
- Transition crossing ← Needed additional tuning
- Bunch rotation to reduce the dp/p for transfer to the Recycler/MI
- Measured Beam Transmission Efficiency and Emittances @Inj & @Exit


Beam Experiments & EIS in Operation




- ❑ We revisited many LLRF parameters
 - ❑ Curves: Radial-position feedback, Voltage and RF frequency etc.
 - ❑ Turn-on time for many parameters
- ❑ Transition crossing ← Needed additional tuning
- ❑ Bunch rotation to reduce the dp/p for transfer to the Recycler/MI
- ❑ Measured Beam Transmission Efficiency and Emittances @Inj & @Exit

Late 2015 we have made the EIS in operation
Made many progress and
seen many benefits.

EIS: Acceleration Efficiencies (Beam and Vrf)




EIS: Acceleration Efficiencies (Beam and Vrf)



Fermilab EIS: Acceleration Efficiencies (Beam and Vrf)




Scope Data for 1st 1ms at Injection



Acceleration
ON

Capture and Transmission efficiency
for the first 1ms ~98%







Transmission Efficiency
over the cycle ~95%

Some Samples of Emittance Measurements



Fermilab Booster Data EIS Studies
FB-20160321-EISE1C-15BT-SnpBR-Cycle-2





Issues and Mitigation




- There are a number of issues that we are working on in order to exploit the EIS fully

- The time jitter in the B_{min} relative to the beam injection clock event is $\sim 30\mu\text{sec}$. This jitter is random and arises from ComEd power line frequency. \leftarrow Introduces emittance dilution @Inj.
- A better RF voltage regulation is needed at injection.
- The transition crossing phase jump is delayed w.r.t. clock event. So jitter as large as $\sim 30\mu\text{sec}$. \leftarrow unacceptable for Booster.
- The RF frequency does not follow the Booster dipole magnetic field ramp.
- Bunch rotation at extraction for reduced dp/p

Bmin Jitter at Injection



Phase Jump Jitter at TX



Addressing these Issues also Important to PIP-II



Parameter	PIP	PIP-II (After 2022)
Injection Energy (KE) (GeV)	0.4	0.8
Extraction Energy KE (GeV)	8	8
Injection Intensity (p/pulse)	4.52E12	6.63E12
Extraction Intensity (p/pulse)	4.3E12	6.44E12
Repetition Rate	15 Hz	20 Hz
Efficiency (%)	95	97
Booster repetition rate (Hz)	15	20
Booster Beam Power at Extraction	94 kW	184 kW
MI batches	12 every 1.33 sec	12 every 1.2 sec
NOvA beam power	700 kW	1.200MW
Rate availability for other users (Hz)	5	8
Booster flux capability (protons/hr)	~ 2.3E17	~ 3.5E17

PIP and PIP-II parameters with EIS



Potential of Early Injection Scheme

Parameter	PIP	PIP-II (After 2022)
Injection Energy (KE) (GeV)	0.4	0.8
Extraction Energy KE (GeV)	8	8
Injection Intensity (p/pulse)	4.52E12 (X~1.4)	6.63E12
Extraction Intensity (p/pulse)	4.3E12 (~6E12)	6.44E12
Repetition Rate	15 Hz (15 Hz)	20 Hz
Efficiency (%)	95 (≥ 97)	97
Booster repetition rate (Hz)	15	20
Booster Beam Power at Extraction	94 kW (~130 kW)	184 kW
MI batches	12 every 1.33 sec	12 every 1.2 sec
NOvA beam power	700 kW (~950kW)	1.200MW
Rate availability for other users (Hz)	5	8
Booster flux capability (protons/hr)	~ 2.3E17 (3.2E17)	~ 3.5E17