



中国科学院近代物理研究所
Institute of Modern Physics, Chinese Academy of Sciences



中国科学院
CHINESE ACADEMY OF SCIENCES


Lessons of high-power CW beam commissioning of injector II of Chinese ADS

Huan Jia

jiahuan@impcas.ac.cn


Linac group

Institute of Modern Physics, CAS






- **Introduction**
- Experiences and Lessons
- Summary
- Acknowledgment






ADS/ADANES Roadmap in China



Layout of CADS Demo Facility


**Major target of CADS Demo Facility:
Demonstration of the ADS technology
for 10 mA CW beam.**




	RFQ	CM1	CM2	CM3	CM4
frequency	162.5 MHz	162.5 MHz	162.5 MHz	162.5 MHz	325 MHz
output energy	2.1 MeV	5 MeV	10 MeV	17 MeV	25 MeV
cavity type	4-vane	HWR010	HWR010	HWR010	Spoke021
cavity numb	1	6	6	6	6



Milestones of CADS Demo Facility




Summary of beam commissioning



Accelerator	Beam energy	Beam time	CW	CW @ 10 mA
RFQ	2.1 MeV	1390 h	59 h	10 h
TCM1 (1 HWR)	2.5 MeV	208 h	22.5 h	2.5 h
CM1 (6 HWRs)	5 MeV	400 h	20 h	$I_{max} = 4mA$
CM1+CM2 (12 HWRs)	10MeV	Conditioning trouble with couplers		




- Introduction of CADS Injector II
- **Experiences and Lessons**
- Summary
- Acknowledgment






Experiences and Lessons

- **LEBT and RFQ settings**
- **Transverse lattice verification of MEBT**
- **Orbit of MEBT and CM1**
- **Beam power ramping procedure**
- **CW beam and trips**
- **Beam losses with wrong phase setting**
- **1st accident and lessons**
- **2nd accident and lessons**




LEBT and RFQ settings



RFQ Voltage calibrated with energy spread, more precise than Transmission.

T~96 % of RFQ






X ray measurement agrees with energy spread calibration.

RFQ P_c power set point = 100 kW





Transverse lattice verification of MEBT

	α_x	β_x (m/rad)	α_y	β_y (m/rad)	Mismatch factor H/V
From Q1-3 & emittance	0.3	0.25	-0.11	0.12	0.078/0.005
Parmteq simulation	0.46	0.27	-0.10	0.12	reference






Orbit from MEBT to CM1



Beam power ramping procedure


1. 10 mA, 20 us/1 Hz beam, hardware calibration.
2. 10 mA, 20 us/1 Hz beam, lattice verification.
3. 1~2 mA, 20 us/1 Hz to CW, by steps.
4. 2 mA to 10 mA, by steps.



Beam power ramping procedure


No circulator for RFQ, to minimize P_r , RFQ vane water temperature is tuned down by 0.5 °C, i.e. ~ 10 kHz for CW beam loading from 2 mA to 10 mA. Explanation, see **THPM2Y01, Huang Ran, on July 7th afternoon.**

LLRF controlled
Water Mixer for
RFQ stability





Δf : 1.6 kHz \rightarrow 0.5 kHz

Adjustable Aperture
in LEBT smoothly
changed the beam
current





dI: 2 mA \rightarrow 0.1 mA


SARAF Annual
report 2012




CW beam and trips



Jan. 2th, 2016, ~2mA, 4.0 MeV, CW, 7.5 hours



1. P_r overshoot, (from Arc in RF system), interlock LLRF, turn off RF.
2. Wait 50 us, RF recovered to full RF power smoothly in 30 ms.




Beam losses with wrong phase setting







Type: PT100
Normal temperature



LAKE SHORE:DT-670B
2K-305K(±0.5K)



Phase setting determination






All BPM phases have same signs



HWR #2 #5 phase signs are opposite to other cavities.

Phase curve analysis


Not sine-wave






dW/W 0.2 for SC cav and 0.05 for buncher




Cavity Field map model predict TOF in cavity and fit the phase curve.
 Calibrate input phase and amplitude.




A New phase scan App



342 deg




A new phase scan App has been developed, and is successfully used in SC cavity phase settings.



Fixed E_{in}
Fitting Amplitude
and input phase

$$\phi_s = \arctan \left[\frac{\int_{S_0+L}^{S_0} qE_z(s) \cdot \sin[\phi(s)] \cdot ds}{\int_{S_0}^{S_0+L} qE_z(s) \cdot \cos[\phi(s)] \cdot ds} \right]$$

HWR cavity	ΔE (MeV, Meas)	ΔE (MeV, App)
CM1-2	0.16	0.15
CM1-4	0.203	0.206
CM2-2	0.117	0.12
CM2-3	0.095	0.105
CM2-4	0.325	0.312




Date: June 29th 2015

Beam state: 2.5 MeV, 2.7mA, CW, 1 min

Procedure:

1. Two paths are defined to do beam interlock, chopper and HV-IS.
2. Interlock threshold value of BPM was 1.0 volts, relatively lower. The relay to shutdown HV-IS was disabled by triggers due to noise.
3. Chopper can be recover automatically after 13 s.
4. CW beam recovered after 13 s, and damaged the bellow the bending magnet. Vacuum interlock triggered valves and FC at LEBT. They are the actions of MPS.
5. Valve was inserted, but 1 s later than FC was inserted.
6. Secondary accident is the valve damage and the CM leak.







1st accident and lessons



1. Self-check function of MPS may be important. To make sure every action is in order in advance.
2. All trigger levels should be defined carefully, and be free of noise.
3. Beam loss is detected by temperature sensors attached to the beam pipe, and give signal to MPS system.
4. Interlock of Chopper should not recover beam until be reset manually.
5. Action sequences of inserting devices after vacuum leak should be clearly defined to minimize the damage of machine.




2nd accident and lessons



Date: December 4th 2015

Beam state: 4.6 MeV, 3.9 mA, CW, 90s

1. The BPM upstream of FC was out of order.
2. The current value measured by FC became unstable but was neglected.
3. Beam hit the FC off-centered by ~20 mm. It drilled a hole to the water pipe of FC, then water jetted into the vacuum pipe.



4.6 MeV, 3.9 mA,
CW, 90, 1.6 MJ



Water
leakage
of FC



Pump
with
water


2nd accident and lessons

1. Observe beam position on the FC/DUMP/target is important. We developed an optical camera system.
2. Automatically check lattice during beam power ramping up.
3. Do not bypass any MPS signal until it is well understood or you have the other hand to do it.
4. Stop high power beam to analyze any abnormal or strange phenomena.





1. Great progress for beam commissioning of CIADS injector II has achieved during last two years.
2. Transverse lattice is confirmed with field overlap model.
3. Beam structure of 4.95 ns/5 ns with 50 ns gap to utilize the DBCM system.
4. Circulator is important for stable operation of cavities.
5. A new phase scan app is developed to understand beam information, which is critical for linac commissioning.
6. MPS system is a “safe critical” system for high power Superconducting linac.
7. 20~25 MeV, 10 mA, pulse beam commissioning before the end of 2016, collaboration with IHEP.






Acknowledgements



Prof. Wenlong Zhan, CAS
Prof. Yuan He, IMP
Dr. Zhijun Wang, IMP
Dr. Zhouli Wang, IMP
Dr. Wei Chang, IMP
Dr. Zhen Gao, IMP
Ms. Shuhui Liu, IMP
Ms. Haihua Niu, IMP
Ms. Yue Tao, IMP
Ms. Yuqing Wan, IMP
Mr. Weilong Chen, IMP
Mr. Chi Feng, IMP
Mr. Wangsheng Wang, IMP
Mr. Weiping Dou, IMP
Mr. Chenzhang Yuan, IMP
Mr. Qi Wu, IMP





Acknowledgements

Thanks for your attention

Thanks for the helps

from **LBL**, **J-Lab**, **TRIUMF**, ANL, MSU/FRIB, ORNL, FNAL,
RIKEN, CEA/Saclay, IPN/Orsay, IAP, KEK,
HIT, PKU, SINAP,.....

Welcome Collaboration!

